

Commissioning GFCH-3-G

Part number: 8044344

FESTO



 [General operating condition](#)

Data sheet

Feature	Value
Structural design	Triple axis system with safety module CAMC-G-S3
Scope of services	Activation of the axes in test mode Data backup and documentation Instruction of machine operators, e.g. in error diagnostics and eliminating errors or in changing the position values Configuration and parameterization of the axes Optimization of control parameters and homing Checking of wiring, connections, travel paths and energy chains
Work involved on site	9 hours of work
Customer requirements	Use of Festo components CMMP-OS-...-M3 + CAMC-G-S3 Access to the machine or system Wiring of the CAMC completed and checked according to DIN EN 60204 1x "Safety requirements" appendix filled out in full per controller Mechanical, pneumatic and electrical work is completed Qualified personnel responsible for the machine must be present on the agreed date
Provision of services	8-10 days subject to agreement